

数量総括表

	04-11-005	04-13-002	05-03-017	002-301	00-018	計
既設口径	350	250	350	250	350	-
管路延長(m)	29.5	30.93	45.08	58.4	8.70	172.61
管渠延長(m)	28.6	30.03	44.18	57.5	8.25	168.56

施工区分			夜	夜	昼	昼	夜	昼計	夜計	合計
管渠 更生工	既設管内洗浄工		28.6	30.03	44.18	57.5	8.25	101.68	66.88	168.56
	管きよ内被覆工	250		30.03		57.5		57.5	30.03	87.53
		350	28.6		44.18		8.25	44.18	36.85	81.03
	更生管材料	250 4.0mm		30.93				0	30.93	30.93
		250 5.0mm				58.4		58.4	0	58.4
		350 5.0mm					9.15	0	9.15	9.15
		350 6.0mm	29.5					0	29.5	29.5
		350 7.0mm			45.08			45.08	0	45.08
	管口切断工	250		2		2		2	2	4
		350	2		2		2	2	4	6
	管口仕上工	250		2		2		2	2	4
		350	2		2		2	2	4	6
	取付管口せん孔工		5	2	6	3		9	7	16
仮設備	仮設備設置工		1	1	1	1	1	2	3	5
	仮設備撤去工		1	1	1	1	1	2	3	5
換気工	換気設備工		1	1	1	1	1	2	3	5
管きよ 更生水替 工	潜水ポンプ運転工		1	1	1	1		2	2	4
	泥水運搬工 (更生作業時2台待機)						1		1	1
		150以下	2		6	3		-	-	11
		200	3	2				-	-	5
		250	1	1	2		2	-	-	6
		350	1				0	-	-	1
耐震接手工		250		2		2		-	-	4
		350	2		2		2	2	4	6